



Notice Inviting e-Tender

NIT No.: DHE/SKC/CIVIL/NIT(e)-02/2022-23(2nd Call) DATED 01/07/2022

COMMUNICATION ADDRESS:

**P.O. : Bagula, Nadia, Pin : 741502, W.B.
Phone No : (03473) 272205
srikrishnacollegebagula@rediff.com**

Date of Publication of Tender (online): 02/07/2022 AFTER 18.00 HRS.

Last Date of Submission of Bid (online): 16/07//2022 UP TO 18.00 HRS.

E-Tender is invited by the **Principal, Srikrishna College** for various civil works as mentioned above from the technically eligible and financially credible bidders. Interested bidders may follow the instructions as given below for submission of their tenders under online mode through WB e-Tender Portal : <https://wbtenders.gov.in/nicgep/app>

SL NO	NAME OF THE WORK	AMOUNT PUT TO TENDER	EMD AMOUNT	COMPLETION PERIOD
01	Civil work for Construction of New Class Room at existing building top floor(Main building vertical extension) of Srikrishna College, Bagula Campus Dist.- Nadia.. specification given in Annexure -1A	2837052.00	2 % of the amount put to the tender	120 days

EARNEST MONEY DEPOSIT:

Intending bidder should submit Earnest Money Deposit as mentioned above through online payment mode as per the policy of the WB e Tender Portal. Bidders are required make payment of Earnest Money (EMD) through the e-Payment banking system, on-line and should read in advance the instructions carefully, particularly those contained in the challan generated in the e-transaction of the portal, if opted for EMD payment through RTGS/NEFT.

ELIGIBILITY CRITERIA/ DOCUMENT TO BE SUBMITTED:

Intending bidders must submit the following documents for participation in tender to the respective folder as mentioned in the Tender:

1. Pan Card of the Applicant/Organization.
2. GST Registration Certificate with copy of the submission of latest return .
3. Partnership Deed /Registration or Incorporation Certificate if Applicable
4. Valid Trade License.
5. ITR details and Profit and loss statement with annual average turnover not less than 50 lac for each year of last three years.
6. Professional Tax Registration Certificate with up to date Challan Copy.
7. Past Experience Certificate from the Govt. Department/Organization in similar nature of

Job/Work as following.

- A. A Single order amounting at least 60 % of the reserve price.
- B. Two orders amounting at least 50 % of the reserve price.
- C. Three orders amounting at least 40 % of the reserve price

- 8. Declaration/undertaking that the bidder is not blacklisted by any Govt. Organization.
- 9. Signed Copy of All Annexure and affidavit as prescribed format.

GENERAL TERMS AND CONDITION:

- 1. **Validity of Bid:** The bid quoted by the bidder shall valid for 120 days. Workr shall have the right to work the goods/items with same quoted rate within the period of bid validity.
- 2. **Payment Terms:** Payment shall be made within 30 days from the date of installation of the items/ goods
- 3. **Price:** Price should be inclusive of all taxes and statutory charges. No extra charges shall be given to the successful bidder
- 4. **Completion Period:** The entire work executed and completed within the completion period as mentioned.
- 5. The quantity of the items may be increased or decreased in the actual work order actual requirement. Bidder/Supplier shall be bind to deliver and install any nos. of items/goods of the similar kind of product at the same quoted L1 rate with in the period of Bid Validity.
- 6. **Defect Liability:** The defect liability period is 1 year from the date of completion of the Work. The successful bidders shall be liable & responsible solve and repair for all kind of defect or damages if arise within the one years from the date of completion of work.
- 7. **Liquidity Damages/ Delay in Delivery of Installation:** 1 % per week of the order value will be applicable for belated supply towards liquidated damages subject to maximum of 10 % beyond the due date. Such amount will be deducted from any amount due or which may become due to supplier. There after the Bid Security of Earnest money deposit of the bidder may be forfeited.
- 8. **Supporting Equipment:** Successful bidders shall be liable to carry their won equipment for execution and successful completion of the job. No extra cost shall be applicable to the tender inviting authority.

- 9. Service Facility:** Successful bidder should have good service facilities if require during the period of defect liability and even after the same. Adequate document to after sale service to furnished along with the bid documents.
- 10. Terms of Execution:** The Bidders shall be responsible for all losses and damages from any cause whatsoever while the work is going on or is in the course of execution of work and related transit to the College. The cost of the transit insurance and transport should be borne by the successful Bidder.
- 11.** Before bidding, the Bidder may visit the site, at their own cost, to satisfy themselves about the local conditions and constraints and other matters. The Bidder shall be presumed to have carefully examined General Terms and Conditions, Technical Specifications, BOQ etc. and have fully acquainted themselves with all details of site location, work front, site constraints, communications, materials, labors, water supply position, electricity and any other general information pertaining to and needed for the work to be completed within stipulated period, and shall quote accordingly taking all these factors into account. No claim whatsoever on the ground of insufficient knowledge about the work site or local condition will be entertained..
- 12.** The Authority reserve all rights to reject any bid including of those bidders who fail to comply with the instructions without assigning any reason whatsoever and does not bind it to accept the lowest or any specific bid. The decision of the College in this regard shall be final and binding.
- 13.** Any failure on the part of the bidder to observe the prescribed procedure and any attempt to canvas in any form at any stage are liable for cancellation of bid.
- 14. Performance Security:** 3 % of the order value to be deposited as performance security for 45 days beyond the warrant period.
- 15.** Quantity may be increase or decrease in the work order or additional order may be place for listed item during the period of bid validity. Bidders shall be liable to complete the work with the same rate of quoted price during this period.
- 16.** Contractor shall have to comply with the provisions of (a) the contract labor (Regulation Abolition) Act. 1970(b) Apprentice Act. 1961 and (c) minimum wages Act. 1948 of the

notification thereof or any other laws relating thereto and the rules made and order issued there under from time to time.

- 17.**Penalty for suppression / Distortion of facts: Submission of false document by tenderer is strictly prohibited and in case of such act by the tenderer the same may be referred to the appropriate authority for prosecution as per relevant IT Act with forfeiture of earnest money forthwith.
- 18.**The Employer (tender accepting authority) reserves the right to accept or reject any Bid and to cancel the Bidding processes and reject all Bids at any time prior to the award of Contract without thereby incurring any liability to the affected Tenderer or Tenderers or any obligation to inform the affected Tenderer or Tenderers of the ground for Employer's (tender accepting authority) action.
- 19.**The Tenderer who's Bid has been accepted will be notified by the Tender Inviting and Accepting Authority through acceptance letter/ Letter of Acceptance. The Letter of Acceptance will constitute the formation of the Contract.
- 20.**The Agreement in Printed Tender Form will incorporate all necessary documents e.g. N.I.T., all addenda-corrigendum, special terms and condition, different filled-up forms, Price Schedule and the same will be executed between the Tender Accepting Authority and the successful Tenderer.

SD /
PRINCIPAL
SRIKRISHNA COLLEGE

ANNEXURE-IA

SOQ (SCHEDULE OF WORKS)

ITEM LIST/SPECIFICATION& COMPLIANCE STATEMENT

SCHEDULE : A

Name of the work: Civil work for Construction of New Class Room at existing building top floor of Bagula College Campus Dist.- Nadia..

SL No	Description of item	Quantity	Unit	Rate	Amount
1.00	M.S. structural works with hollow sections (square or rectangular shape) conforming to IS: 806-1968 & IS:1161-1998) connected to one another with bracket, gusset, cleat as per design, drawing & direction of Engineer-in-Charge complete including cutting to requisite shape & size, fabrication including metal arc welding conforming to IS: 816-1969 & IS: 9595 using electrodes of approved make and brand conforming to IS:814- 2004, haulage, hoisting and erection all complete. The rate includes the cost of all M.S. Hollow section, all consumables such as electrodes, gas and hire charges of all tools and plants and labour required for execution and all incidental charges (such as electricity, labour insurance) etc. complete.	8.00	MT		
2.00	M.S. structural works in columns, beams etc. with simple rolled structural members (e.g. joists, angle, channel sections conforming to IS: 226, IS: 808 & SP (6)- 1964 connected to one another with bracket, gussets, cleats as per design, direction of Engineer-in charge complete including cutting to requisite shape and length, fabrication with necessary bolting, metal arc welding conforming to IS: 816- 1969 & IS: 1995 using electrodes of approved make and brand conforming to IS:814- 2004, haulage, hoisting and erection all complete. The rate includes the cost of rolled steel section, consumables such as electrodes, gas and hire charge of all tools and plants and labour required for the work including all incidental charges such as electricity charges, labour insurance charges etc.	1.20	MT		
3.00	125mm thick brick work (1:4).	20.00	Sqm		
4.00	Neat cement punning	45.00	Cum		
5.00	Galvanised iron sheet ridging fitted with necessary bolts, screws, washers etc complete.(225mm end lapping).(A) 300 mm lapping each way.(b) With 0.63 mm sheet	27.00	M		

6.00	Supplying, fitting & fixing Zn-Al alloy (55% Al & 45% Zn) coating of 150 grams per sq. metre (followed by colour coated on both side) steel sheet work having minimum yield strength of 550 Mpa of trapizoidal profile of approved make (excluding the supporting frame work) fitted and fixed with 55 mm & 25 mm self tapping screw, EPDM Washer 16 mm dia & 3 mm th. washer etc. complete with 150 mm end lap and one corrugation minimum side lap. (Payment to be made on area of finished work)(i) In Roof:- a) With 0.5 mm thick sheet	520.00	Sqm		
7.00	Wood work in posts, post plates, rafters, battens, truss members, purlins etc. fitted and fixed complete (excluding the cost of bolts, paints, but including the cost of nails, screws etc.) (d) Sal : Local	2.00	Cum		
8.00	Artificial stone in floor, dado, staircase etc with cement concrete (1:2:4) with stone chips, laid in panels as directed with topping made with ordinary or white cement (as necessary) and marble dust in proportion (1:2) including smooth finishing and rounding off corners including raking out joints or roughening of concrete surface and application of cement slurry before flooring works using cement @ 1.75 kg/sq.m all complete including all materials and labour. In ground floor.3 mm. thick topping (High polishing grinding on this item is not permitted with ordinary cement). Using grey cement (ii) 35 mm. thick	350.00	Sq.M.		
9.00	Ordinary Cement concrete (mix 1:1.5:3) with graded stone chips (20 mm nominal size) excluding shuttering and reinforcement if any, in ground floor as per relevant IS codes. (i) Pakur Variety	22.000	Cum		
10.00	Supplying solid flush type doors of commercial quality, the timber frame consisting of top and bottom rails and side styles of well seasoned timber 65mm wide each and the entire frame fitted with 37.5mm wide battens places both ways in order to make the door of solid core and internal lipping with Garjan or similar wood veneers using phenol formaldehyde as glue etc. complete, including fitting, fixing shutters in position but excluding the cost of hinges and other fittings in ground floor (a) 35 mm thick shutters (single leaf	13.00	Sq.M.		
11.00	Supplying, fitting and fixing hinge cleat in position excluding the cost hinge and other fittings.a) with 50mm iron Butt-hinge iii) Local Sal.	6.00	Each		
12.00	Supplying, fitting and fixing M.S. clamps for door and window frame made of flat bent bar, end bifurcated with necessary screws etc. by cement concrete(1:2:4) as per irection. (Cost of concrete will be paid separately) (a) 40mm X 6mm, 250mm Length	10.00	Each		
13.00	Iron butt hinges of approved quality fitted and fixed with steel screws, with ISI mark.(vi) 100mm. X 50mm. X 1.25mm	20.00	Each		
14.00	Door stopper (Anodised aluminium)	5.00	Each		
15.00	Anodised aluminium barrel / tower / socket bolt (full covered) of approved manufactured from extruded section conforming to I.S. 204/74 fitted and fixed with cadmium lated screws: (vi) 200mm long x 10mm dia. bolt.	10.00	Each		

16.00	Anodised aluminium Aldrop / Sliding bolts of approved quality manufactured from extruded section conforming to I.S. specification (I.S. 2681/66) fitted and fixed complete. (i) 250mm x 16mm dia bolt	5.00	Each		
17.00	Anodised aluminium D-type handle of approved quality manufactured from extruded section conforming to I.S. specification (I.S. 230/72) fitted and fixed complete: (iv) 125 mm grip x 10 mm dia rod	10.00	Each		
18.00	Rubber buffer block	5.00	Each		
19.00	15mm thick ply partition.	140.00	Sqm		
20.00	Plaster (to wall, floor, ceiling etc.) with sand and cement mortar including rounding off or chamfering corners as directed and raking out joints including throating, nosing and drip course, scaffolding/staging where necessary (Ground floor).[Excluding cost of chipping over concrete surface] (i) With 1:6 cement mortar (b) 20 mm thick plaster	660.00	Sq.M.		
21.00	Protective and Decorative Acrylic exterior emulsion paint of approved quality, as per manufacturer's specification and as per direction of Engineer-in-Charge to be applied over acrylic primer as required. The rate includes cost of material, labour, scaffolding and all incidental charges but excluding the cost of primer. Normal Acrylic Emulsion	330.00	Sq.M.		
22.00	Applying Exterior grade Acrylic primer of approved quality and brand on plastered or concrete surface old or new surface to receive decorative textured (matt finish) or smooth finish acrylic exterior emulsion paint including scraping and preparing the surface thoroughly, complete as per manufacturer's specification and as per direction of the EIC.(b) Two Coats	330.00	Sq.M.		
23.00	(a) Priming one coat on steel or other metal surface with synthetic oil bound primer of approved quality including smoothening surfaces by sand papering etc.	455.00	Sqm		
24.00	(A) Painting with best quality synthetic enamel paint of approved make and brand including smoothening surface by sand papering etc. including using of approved putty etc. on the surface, if necessary : (b) On steel or other metal surface :				
24.10	With other than hi-gloss of approved quality- (iv) two coats (with any shade except white)	455.00	Sqm		
26.00	M.S. gate of Jail type as per approved design made of strong M.S. frame work, intermediate stiffeners and round / square bars or angles. M.S. sheet (not less than 14 gauge) ussets, cleats etc. including necessary riveting, bolting, welding, locking and hanging arrangements, fitting and fixing complete as per direction of the Engineer-in -charge.	0.60	Qntl		

27.00	Supplying, fitting & fixing 1st quality Ceramic tiles in walls and floors to match with the existing work & 4 nos. of key stones (10mm) fixed with araldite at the back of each tile & finishing the joints with white cement mixed with colouring oxide if required to match the colour of tiles including roughening of concrete surface, if necessary or by synthetic adhesive & grout materials etc.				
	(A) Floor : With Sand Cement Mortar (1:4) 20 mm thick & 2 mm thick cement slurry at back side of tiles using cement @ 2.91 Kg/Sq.m & joint filling using white cement slurry @ 0.20kg/Sq.m. (a) Area of each tile upto 0.09 Sq.m (i) Coloured decorative	5.00	Sqm		
	(B) Wall: With Sand Cement Mortar (1:3) 15 mm thick & 2 mm thick cement slurry at back side of tiles using cement @ 2.91 Kg/Sq.m & joint filling using white cement slurry @ 0.20kg/Sq.m. (a) Area of each tile upto 0.09 Sq.m (i) Coloured decorative	20.00	Sqm		
28.00	Applying Exterior grade Acrylic primer of approved quality and brand on plastered or concrete surface old or new surface to receive decorative textured (matt finish) or smooth finish acrylic exterior emulsion paint including scraping and preparing the surface thoroughly, complete as per manufacturer's specification and as per direction of the EIC. (a) One Coat	330.00	Sqm		
29.00	Protective and Decorative Acrylic exterior emulsion paint of approved quality, as per manufacturer's specification and as per direction of Engineer-in-Charge to be applied over acrylic primer as required. The rate includes cost of material, labour, scaffolding and all incidental charges but excluding the cost of primer. a) Normal Acrylic Emulsion	330.00	Sqm		
30.00	Supplying fitting and fixing in position approved P.V.C. door frame (Matt finish) made of extruded P.V.C. multichamber hollow section having dimensions 60mm x 50mm x mm (+/- 0.2mm), horizontal section will be joined with vertical section by galvanised steel screws after inserting two number steel brackets as reinforcement making suitable space for placing hinges, one steel tube 40mm x 20mm x 1.20 mm will be inserted on one full vertical side of the frame (hinge side) as reinforcement, the frame will then be fixed in the opening with the help of P.V.C. expandable fastener/wooden gutties and galvanised steel screws including cost of all materials and labour, hire charges of tools and appliances, carriage of all materials, taxes and all other incidental charges complete.	10.00	Rm		

31.00	PVC Door Shutter-37 mm thick: Supplying fitting and fixing P.V.C. door shutter of approved quality & shade in position, the style & rail of the P.V.C. door shutter will be made of rigid P.V.C. multicavity hollow chamber of suitable size and section with 2.0 mm (+/-0.2 mm) wall thickness, the section will have 2nos. built in beads, horizontal & vertical section shall be fixed to each other by self tapping screws and 2 nos. of solid plastic or M.S. tubular galvanised brackets of length 200mmx80mm and other 100mmx100mm both 1.20 mm in each corner of the shutter frame for placing hinges. Polymer based multicavity hollow section of 105 mm x37mm with 2.0 mm (+/- 0.2 mm) wall thickness will be fitted in the middle as lock rail reinforced by solid polymer bar of 200 mm long at both ends and screws from both sides. The section frame will then be fitted in by PVC panels of size 100 mmx20 mm with wall thickness of 1.2 mm (+/- 0.2 mm) and 2 nos. of 6 mm dia and screws from both sides 6mm dia bright rod will be inserted horizontally with both side check and nut system and stretches where fixing of hinges / hasp bolt / tower bolt / door ring are required to be strong enough to with stand wear and tear. The rate is inclusive of cost of all materials, labour, and hire of tools and plants and appliances. Carriage of all materials taxes and all other incidental charges complete. The rate is inclusive of cost of hinges, hasp bolt, tower bolt, door ring etc. In ground floor.	4.00	Sqm		
32.00	Priming one coat on timber or plastered surface with synthetic oil bound primer of approved quality including smoothening surfaces by sand papering etc	175.00	Sqm		
33.00	Hire and labour charges for shuttering with centering and necessary staging upto 4 m using approved stout props and thick hard wood planks of approved thickness with required bracing for concrete slabs, beams and columns, lintels curved or straight including fitting, fixing and striking out after completion of works (upto roof of ground floor)				
34.00	(a) 25 mm to 30 mm thick wooden shuttering as per decision & direction of Engineer-In-Charge.	125.00	Sq.M.		
35.00	Reinforcement for reinforced concrete work in all sorts of structures including distribution bars, stirrups, binders etc initial straightening and removal of loose rust (if necessary), cutting to requisite length, hooking and bending to correct shape, placing in proper position and binding with 16 gauge black annealed wire at every intersection, complete as per drawing and direction. (a) For works in foundation, basement and upto roof of ground floor / upto 4m (i) Tor steel/Mild Steel : SAIL/TATA/RINL	2.20	Mt		
36.00	Supplying, fitting and fixing PVC pipes of approved make of Schedule 80 (medium duty) conforming to ASTM D - 1785 and threaded to match with GI Pipes as per IS : 1239 (Part - I). with all necessary accessories, specials viz. socket, bend, tee, union, cross, elbo, nipple, long screw, reducing socket, reducing tee, short piece etc. fitted with holder bats clamps, including cutting pipes, making threads, fitting, fixing etc. complete in all respect including cost of all necessary fittings as required, jointing materials and two coats of painting with approved paint in any position above ground. (Payment will be made on the centre line measurements of total pipe line including all specials. No separate payment will be made for accessories, specials. Payment for painting will be made separately) (a) For Exposed Work PVC Pipes				
	a) 15mm dia	12.00	Rm		
	b) 20mm dia	16.00	Rm		

	c) 25mm dia	19.00	Rm		
	d) 32 mm dia	18.00	Rm		
37.00	Supplying, fitting and fixing gunmetal wheel valve of approved brand and make tested to 21 kg per sq. cm. (for water lines only).				
	a) 15mm dia	6	Each		
	b) 20mm dia	5	Each		
	c) 25mm dia	4	Each		
	d) 32 mm dia	2	Each		
38.00	Chromium plated Bib Cock long body with wall flange with aerator (Equivalent to Code No. 512 & Model - Tropical / Sumthing Special of ESSCO or similar brand)	10	Each		
39.00	Chromium plated Concealed Stop Cock (Equivalent to Code No. 514(A) & Model - Tropical / Sumthing Special of ESSCO or similar brand).	10	Each		
40.00	Supplying, fitting and fixing white vitreous china best quality approved make wash basin with C.I. brackets on 75 mm X 75 mm wooden blocks, C.P. waste fittings of 32 mm dia., one approved quality brass C.P. pillar cock of 15 mm dia., C.P. chain with rubber plug of 30 mm dia., approved quality P.V.C. waste pipe with C.P. nut 32 mm dia., 900 mm long approved quality P.V.C. connection pipe with heavy brass C.P. nut including mending good all damages and painting the brackets with two coats of approved paint. (ii) 550 mm X 400 mm size	2	Each		
41.00	Supplying, fitting and fixing approved brand P.V.C. CONNECTOR white flexible, with both ends coupling with heavy brass C.P. nut, 15 mm dia. (iii) 600 mm long	6	Each		
42.00	Supplying, fitting and fixing Anglo-Indian W.C. in white glazed vitreous china ware of approved make complete in position with necessary bolts, nuts etc. (a) With 'P' trap (with vent)	2	Each		
43.00	Supplying, fitting and fixing Squating plate with integral flushing in white vitreous chinaware of approved make in cement concrete (6:3:1) with jhama chips complete. Payment of concrete will be paid seperately). (i) 450 mm X 350 mm	2	Each		
44.00	Supplying, fitting and fixing Closet seat of approved make with lid and C.P. hinges, rubber buffer and brass screws complete. (b) Anglo Indian (ii) Plastic (hallow type) white	2	Each		
45.00	Supplying, fitting and fixing bevelled edged mirror 5.5 mm thick silver red as per I.S. 3438 / 1965 together with brass C.P. hinges. (ii) 600 mm X 450 mm	2	Each		
46.00	Supplying, fitting and fixing glass shelf with aluminium guard rails. (a) Ordinary type with 5.5 mm sheet glass (ii) 600 mm X 125 mm	2	Each		
47.00	Supplying, fitting and fixing liquid soap container. (a) Cromium plated	2	Each		
48.00	Supplying, fitting and fixing towel rail with two brackets. (a) C.P. over brass (ii) 25 mm dia. and 600 mm long	2	Each		

49.00	Supplying, fitting & fixing UPVC pipes A- Type and fittings conforming to IS:13592-1992 with all necessary clamps nails, including making holes in walls, floor etc. cutting renches in any soil through masonry concrete structures etc if necessary and mending good damages including joining with jointing materails (Spun Yarn, alamoid/Bitumen/M-Seal etc) complete.				
49.10	110 mm. Dia.	22	M		
49.20	110 mm. Dia. Plain tee	8	Each		
49.30	110 mm. Dia. Bend	12	Each		
49.40	110 mm. Dia. Shoe	5	M		
50.00	Supplying, fitting and fixing 10 litre porcelain low-down cistern of approved make with either side or bottom inlet, side overflow, brackets complete with all internal PVC fittings. White	2	Each		
51.00	M.F. suspended ceiling made with 12.5 mm thick Gypsum plaster board including G.I. perimeter channel of 0.55 mm flush (having two flanges 20 mm and 30 mm respectively and web 27 mm) along with perimeter of ceiling with G.I. intermediate channel of 0.9 mm thick size 45 mmx15mm placed at 750 mm c/c with G.I. ceiling angle of size 25 mx10mmx0.55 mm thick fixed to the ceiling with G.I. Cleat and steel expansion fastener ceiling section 0.55 mm thick of size 51.50 mmx26mm fixed to the intermediate hannels with the help of connecting clip and in the direction of perpendicular to the intermediate channel of 300 mm c/c 12.5 mm thick Gypsum plastered board are to be ixed under ceiling section as above by machine screws. The boards are to be joined and finished with jointing compound, paper tape and application of top coat etc. as per the direction of Engineer-in-charge. (The rate includes of cost of all materials including taxes, cost of accessories, fittings and fixtures, scaffolding and labour charges etc. complete) In ground floor	328.00	Sqm		
52.00	Painting with best quality synthetic enamel paint of approved make and brand including smoothening surface by sand papering etc. including using of approved putty etc. on the surface, if necessary :(a) On timber or plastered surface :With other than hi-gloss of approved quality-(iv) Two coats (with any shade except white)	175.00	Sqm		

CHECKLIST:

NAME OF THE BIDDER : _____

ADDRESS OF THE BIDDER : _____

CONTACT NO. : _____

EMAIL ID: : _____

SL NO.	PARTICULARS	REMARKS
1	Whether Submitted the Detailed of Earnest money Deposit or uploaded proper exemption documents.	
2	Pan Card of the Applicant/Organization	
3	GST Registration Certificate with copy of the submission of latest return	
4	Partnership Deed /Registration or Incorporation Certificate if Applicable	
5	Valid & up to date Trade License	
6	ITR details of last three years	
7	Professional Tax Registration Certificate with up to date Challan Copy	
8	Past Experience Certificate from the Govt. Department/Organization in similar nature of Job/Work	
9	Declaration/undertaking that the bidder is not blacklisted by any Govt. Organization	
10	Declaration/undertaking that the bidder is agreed to attend/rectify/replace the defected good within 2 - 4 working days from receipt of the same from the College during the warranty period	
11	Signed Copy of All Annexure and Compliance Statement as per Tender	

Seal and Signature of the Bidder

**UNDERTAKING
AFFIDAVIT-Y**

[TO BE GIVEN ON NON-JUDICIAL STAMP PAPER]

NIT NO. WITH DATE: _____

I, _____ (NAME OF THE SIGNATORY), _____ (DESIGNATION)
of _____ (NAME OF COMPANY/FIRM) _____
_____ (REGISTERED ADDRESS) hereby undertake the following:

- 1) My organization/ constituent or any personnel associated with it, neither have abandoned any work nor any of our contract have been rescinded during the last 5 (five) years.
- 2) Our Company/Firm have never been blacklisted by any Govt. Organization or by any others statutory body.
- 3) I have read the tender documents and understood the all terms and conditions and the scope of the works and abide by them.
- 4) The undersigned understand that Tender Inviting authority reserve the right to make amendment of the scope of works or terms and condition and also has the right to cancel the tender or bid without assigning any reason:

Name of Authorized Signatory:**Designation:****Contact Number:****Signature and seal of the Bidder**